

LOLER Thorough Examination Checklist

A quick-reference checklist used by our engineers for every safety checks engagement. Print and bring to site, or share with your facilities team.

- Verify previous report and remedial actions closed
- Inspect suspension means (ropes/belts) for wear
- Test overspeed governor and safety gear
- Check buffers and final limit switches
- Examine door interlocks and locking devices
- Verify load plate and SWL signage
- Test alarm, intercom and emergency lighting
- Issue digital LOLER report within 48 hours

Questions? Email service@angellifts.co.uk — a senior engineer will respond the same working day.